Product Pine Interior	ref. 9086 / Ocala	Qty	Sales Price	Total Price
38x24 Monitor Horse Barn (3) 12x12 Stalls (1) 12x12 Tack Room 14' Aisle		1.0	\$91,490.00	\$91,490.00
LP Smartside Board & Batten Siding Architectural Shingle Color:				
PACKAGE INCLUDES: Freight and Set Up on Customer Prepared Site per All Anchoring Material On Site Lift Complete Set of Shop Drawings (Note: Architectural Stamped Drawings, If Needed for an Additional Fee)				
STANDARD FEATURES INCLUDE: Pressure Treated 6x6 Perimeter Steel Re-enforced Corners with Built-In Tow Hoo 2x4 Oak Framing 4' High Oak Kick Board in Stalls 1/2" OSB Roof Sheathing	ks			
 2x8 Tongue & Groove Yellow Pine Aisle Walls 15 lb. Felt Paper 30 Yr. Architectural Shingles All Hardware Horse Head Door Latches, Hinges, 6 STALLS INCLUDE: Grill Front(s) w/Sliding Door Fronts 	rtc.			
- Window with Powder-Coated Steel Bars - Solid or Grill Partition - Split Sliding Door's Each End of Aisle TACK/FEED ROOM INCLUDES: - Service Door - Slider Window				
- 5/8" Plywood Floor				

SEE BELOW FOR SECOND FLOOR SPECS



Product Pine Interior ref. 9086 / Ocala	Qty	Sales Price	Total Price
PLEASE NOTE: Natural Oak Kickboard May Show Dark Weathering Marks, Splintering, and Cracking. Upgraded Kickboard Is Available If Preferred. 6x6 Base Is For Delivery and Structural Purposes Only. Covering These With Mats/Stonedust Is Recommend as Chipping and Cracking May Occur During Delivery.			
10' Overhang - Includes Upgrading Wall Height and Building Entire Roof On Site	1.0	\$15,125.00	\$15,125.00
Jpgrade Stall Window to Dutch Door with Glass Insert & Protective Grill	3.0	\$625.00	\$1,875.00
add Windows to Sliding Aisle Door	4.0	\$625.00	\$2,500.00
Jpgraded Siding To LP Smartside Board and Batten Siding - Includes All Paint	1.0	\$7,625.00	\$7,625.00
Second Floor Components:	1.0	\$0.00	\$0.00
12' x 6' Pressure Treated Deck w/ Pressure Treated Decking and railing	1.0	\$17,425.00	\$17,425.00
ncludes 6' Double House Doors w/ 15 Lite Glass Includes Extended Roof Overhang Includes Wooden Stairs			
Frame Out Interior Walls With Standard 2" x 4" Framing - Includes 4 Wooden Interior Doors (Exterior Walls are 2"x 6")	1.0	\$2,350.00	\$2,350.00
Spray Foam Loft Floor, and Insulate Walls and Roof With R-21 Insulation	1.0	\$4,125.00	\$4,125.00
Finish Interior Walls With Pine Tongue and Groove - 8 Inch Reveal - Includes Clear Coat Stained Finish	1.0	\$8,490.00	\$8,490.00
Appliance Package (Package can not be separated) - Includes Hookups and installation - Stove - Electric Summit Induction - Fridge - Haier Stainless Steel - Does Not Include Washer/Dryer (Recommend Installing In Tack Room)	1.0	\$3,200.00	\$3,200.00
Cabinetry and Counter Top Package: • Quartz Counter Tops • Kitchen Cabinets Include: Double Doors Under Sink, 2 Drawers • Bathroom Cabinets Include: Double Cabinet Doors Under Sink	1.0	\$8,430.00	\$8,430.00
Plumbing: Inset Walk In Shower Kitchen and Bathroom Sink Connecting Water Lines For Full System and Hookup Point Near Tack Room Toilet and Shower Piping With Exit Hook Up Point 20 Gallon Water Heater – Electric	1.0	\$8,160.00	\$8,160.00
Standard Electrical Package With Breaker Box	1.0	\$4,705.00	\$4,705.00
8 Interior Recessed Lights 10 Interior Outlets			
LG 9,000 BTU Heating and Cooling Mini Split System: Standard Effciency 2 Zones 17 Seer Maximum Sound Level 48 DB (Very Quiet) Includes Exterior Mount Includes 10 year parts and compressor warranty when registered online	1.0	\$7,550.00	\$7,550.00
- TO SECOND CONTROL OF SECOND			



Product Pine Interior ref. 9086 / Ocala	Qty	Sales Price	Total Price
Upgrade Second Floor Windows To 36" x 41" Insulated White Silverline Windows - Low E Grids		\$625.00	\$3,125.00
Architectural Sealed Plans - Stamped By State Licensed Engineer	1.0	\$4,500.00	\$4,500.00
Note: Customer is responsible for site preparation per Horizon Structures diagram. Customer is responsible for providing a minimum of 16' clearance for the delivery driver.	1.0	\$0.00	\$0.00
Payment Terms: \$2,000 Payment for Deposit towards the project is required to get a complete set of drawings (Non-Refundable). Due to the volatile lumber market price of building may change until 35% payment is applied.	1.0	\$0.00	\$0.00
Additional 3% added to the final amount if a credit card is used for any payments above \$5,000.			
35% of the balance (cash or check) and a signed Invoice is required prior to placing your order into the build schedule. This deposit will also guarantee the pricing for 6 months from time of 35% deposit.			
An additional 55% of total project amount is due (cash or check) two weeks prior to delivery. The 10% Final payment is due on the last day the crew is on site. Customer agrees to pay 2% interest per month on any remaining balance due 30 days after completion.	,		
NOTE: Before sending any wire payments please call the office to confirm wiring info.			

TOTAL: \$ 194,135.00

Includes delivery / set-up within 100 miles of Ocala, FL